

## **SCHEDULE OF SUPPLIES/SERVICES**

**Note: The following project description is for the purpose of general information and is not intended to include and describe every feature or item or to define the scope of work.**

**PROJECT DESCRIPTION:** Contractor shall provide all supervision, labor, material and equipment for the following work located at the Defense Distribution Depot Susquehanna (DDSP):

Project No. 3632 – Replace Roofs at Building 54 (West Offices, Bay 1 and Generator Room, Bay 2) and Bldgs 73, 75 and 77.

Project No. 3684 - Repair/Replace Front Roof at Building 351.

Project No. 3640 - Roof Replacement at Building 104.

This requirement consists of performing work, but not limited to, as summarized below:

Project No. 3632 – Replace Roofs at Bldg 54 (West Offices, Bay 1 and Generator Room, Bay 2) and Bldgs 73, 75 and 77. Remove entire existing built-up roof system down to the existing roof structure including all flashing and termination materials. Install a new single-ply .060” EPDM roofing system with new gutters, downspouts, metal flashings and terminations as indicated on the Contract Documents.

Project No. 3684 – Repair/Replace Front Roof at Building 351. Remove existing built-up roof system down to the existing roof structure including all flashing and termination materials where indicated on the Contract Documents. Install a new single-ply .060” EPDM roofing system, gutters, downspouts, metal trim and terminations. Proposed EPDM will tie into an existing EPDM roof system and an existing built-up roof system as indicated on the Contract Documents.

Project No. 3640 – Roof Replacement at Bldg 104. Remove entire existing built-up roof system down to the existing roof structure including all flashing and termination materials. Install a new single-ply .090 EPDM roofing system, gutters, downspouts, metal trim and terminations and a Pre-Vegetated Modular Green Roof System or alternatively remove entire existing built-up roof system down to the existing roof structure including all flashing and termination materials and install a new single-ply .060” EPDM roofing system, gutters, downspouts, metal trim and terminations as indicated on the Contract Documents.

Note: Roof Replacement at Bldg 104 is found under CLIN 0006 and CLIN 0007, which are optional bid items. Either CLIN 0006 or CLIN 0007 will be awarded. Contractor must price both CLIN 0006 and CLIN 0007.

All work shall be performed complete and in accordance with the specifications and drawings dated May 2009.

Davis Bacon Wage Determination Number PA080010 Modification 33 dated 01/15/2010 applies.

**BIDDER'S SCHEDULE**

**PROJECT NO. 3632 - REPLACE ROOFS AT BUILDING 54 (WEST OFFICES, BAY 1 AND GENERATOR ROOM, BAY 2) AND BUILDINGS 73, 75 AND 77  
PROJECT NO. 3684 - REPAIR/REPLACE FRONT ROOF AT BLDG 351  
PROJECT NO. 3640 - ROOF REPLACEMENT BUILDING 104**

**CLIN 0001 Building 54 (West Offices and Generator Room)**

**0001AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation and reinforced .060" inch thick fully adhered EPDM total roofing system as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document 0027-1002  
WBS Element P.2010.00092.001

**0001AB**\_– All costs for the necessary labor, material and equipment required to perform the following tasks:

1. Accompany the COR for the inspection of the roof decking.
2. Protection of government personnel and compliance with Section 02220 Demolition.
3. Removal of all deteriorated decking, including decking with visible dry rot, brown rot, fungus, saturated, swelled or otherwise deformed.
4. Remove deteriorated decking back to the limits of sound decking.
5. Only remove full board widths and terminate removal over roof framing members.
6. Removal of small, deteriorated areas shall be enlarged so that removal area extends over at least three framing members.
7. Installation of new roof decking in place of the deteriorated deck that was removed shall be in accordance with Section 06100 Rough Carpentry.

Estimated Quantity: 100 square feet @ \$\_\_\_\_\_/square feet = \$\_\_\_\_\_.

BOSS Document 0027-1002  
WBS Element P.2010.00092.001

**Total Estimated Amount CLIN 0001** \$\_\_\_\_\_

**CLIN 0002 Building No. 73**

**0002AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation and reinforced .060" inch thick fully adhered EPDM total roofing system as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document 0027-1003  
WBS Element P.2010.00092.002

**0002AB** - All costs for the necessary labor, material and equipment required to perform the following tasks:

1. Accompany the COR for the inspection of the metal roof deck.
2. Protection of government personnel and compliance with Section 02220 Demolition.
3. Removal of all deteriorated metal roof deck, including metal deck with visible holes, areas with severe rust or otherwise deformed.
4. Remove deteriorated metal roof decking back to the limits of sound decking.
5. Only remove full sheets and terminate removal over roof framing members.
6. Installation of new metal decking in place of the deteriorated metal deck.

Estimated Quantity: 50 square feet @ \$\_\_\_\_\_ /square feet = \$\_\_\_\_\_.

BOSS Document 0027-1003  
WBS Element P.2010.00092.002

**Total Estimated Amount CLIN 0002** \$\_\_\_\_\_

**CLIN 0003 Building No. 75**

**0003AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation and reinforced .060" inch thick fully adhered EPDM total roofing system as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document 0027-1004  
WBS Element P.2010.00092.003

**0003AB** - All costs for the necessary labor, material and equipment required to perform the following tasks:

1. Accompany the COR for the inspection of the metal roof deck.
2. Protection of government personnel and compliance with Section 02220 Demolition.
3. Removal of all deteriorated metal roof deck, including metal deck with visible holes, areas with severe rust or otherwise deformed.
4. Remove deteriorated metal roof decking back to the limits of sound decking.
5. Only remove full sheets and terminate removal over roof framing members.
6. Installation of new metal decking in place of the deteriorated metal deck.

Estimated Quantity: 15 square feet @ \$\_\_\_\_\_ /square feet = \$\_\_\_\_\_.

BOSS Document 0027-1004  
WBS Element P.2010.00092.003

**Total Estimated Amount CLIN 0003** \$\_\_\_\_\_

**CLIN 0004 Building No. 77**

**0004AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation and reinforced 060" inch thick fully adhered EPDM total roofing system as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document 0027-1005  
WBS Element P.2010.00092.004

**0004AB** - All costs for the necessary labor, material and equipment required to perform the following tasks:

- 7. Accompany the COR for the inspection of the metal roof deck.
- 8. Protection of government personnel and compliance with Section 02220 Demolition.
- 9. Removal of all deteriorated metal roof deck, including metal deck with visible holes, areas with severe rust or otherwise deformed.
- 10. Remove deteriorated metal roof decking back to the limits of sound decking.
- 11. Only remove full sheets and terminate removal over roof framing members.
- 12. Installation of new metal decking in place of the deteriorated metal deck.

Estimated Quantity: 10 square feet @ \$\_\_\_\_\_/square feet = \$\_\_\_\_\_.

BOSS Document 0027-1005  
WBS Element P.2010.00092.004

**Total Estimated Amount CLIN 0004** \$\_\_\_\_\_

**CLIN 0005 Building No. 351**

**0005AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation and reinforced .060" inch thick fully adhered EPDM total roofing system on the front roof area as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document: 0027-1006  
WBS Element P.2010.00092.005

**Total Amount CLIN 0005** \$\_\_\_\_\_

**CLIN 0006 Building No. 104 (Optional Bid Item)**

**0006AA**- Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install

new polyisocyanurate insulation and reinforced .060" inch thick fully adhered EPDM total roofing system as indicated on the contract drawings and specifications, complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document: 0027-1007  
WBS Element P.2010.00092.006

**Total Amount CLIN 0006** \$\_\_\_\_\_

**CLIN 0007 Building No. 104 – (Optional Bid Item) Pre-vegetated Modular Green Roof System**

**0007AA** - Including the necessary labor, material and/or equipment to perform all work required to remove existing built-up roofing system and insulation in entirety down to the exposed roof structure and install new polyisocyanurate insulation, reinforced **.090" inch** thick fully adhered EPDM roof system and a Pre-vegetated Modular Green Roof System as indicated on the contract drawings and specifications (reference section 07562), complete in-place.

Amount: 1 LS @ \$\_\_\_\_\_.

BOSS Document: 0027-1007  
WBS Element P.2010.00092.006

**Total Amount CLIN 0007** \$\_\_\_\_\_

**TOTAL Estimated Amount (CLINs 0001 thru 0007) = \$ \_\_\_\_\_**

**END OF SCHEDULE OF SUPPLIES/SERVICES**